MYSORE SPECIAL DIVISION.

Notice dated 9th September 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Special Division, Mysore, up to 8th October 1929, till 12 noon for constructing Blocks of Silledar lines at Waddarapalya at Mysore. An abstract of approximate quantities given below. These quantities are not guaranteed. The work should be completed by the end of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M. on the working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one thousand only (1,000) in cash as earnest money and be superscribed "Tender for constructing Blocks of Silledar lines at Waddarapalya at Mysore" in default of which tenders will be rejected.

5. The final acceptance of the tender will rest with the Chief Engineer of Mysore, Bangalore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. No tender stating "percentage less than the lowest tender or as per estimated rates" will be accepted.

10. Once the tender has been accepted no claim for any concessions or higher rates will be entertained.

11. The work to be executed as per D. P. W. Specification.

12. The decision of the Chief Engineer in all matters, regarding measurements, rates, etc., shall be final and legally binding.

ABSTRACT.

	Items of work	Quantity	Per	Rate
1.	Earthwork excavation for foundation and filling in basement, watering and tamping.	166	C.yds.	
2.	Filling foundation with stone-jelly concrete in chunam.	516	C.ft.	
3.	Filling foundation and basement with burnt brick in mortar.	5,761	,,	
4.	Superstructure with burnt brick in clay ...	8,839	,,	
5.	Mud plastering including cowdung washing ...	75·00	Sqr.	
6.	Chunam plastering	161·36	,,	
7.	White and colour washing	248·43	,,	
8.	Flooring with gravel including consolidation ...	150	C.yds.	
9.	Teakwood wrought and put including tarring portions in masonry.	1,176·49	C.ft.	
10.	Roofing with 1st class Mangalore pattern Yalahanka tiles on teak reepers, complete with wood oiling.	134·40	Sqr.	
11.	Providing and fixing ridge tiles set in mortar ...	280	R.ft.	
12.	Cornice 9″ x 9″ over and gable	188	,,	
13.	Burnt stone slabs drain including dressing the joints and cement painting, etc., complete in front of stables.	572	,,	
14.	Stone slabs 6″ thick nicely dressed 2 lines for bed plates of bessemers.	186·5	S.ft.	
15.	Stone slabs including rounding at top and fixing, complete for barricading horses.	875	,,	
16.	Boring holes in the barricading stones	200	Each	
17.	Burnt stone pillars	644	S.ft.	
17a.	Dressing the above 2 lines	1,932	,,	
18.	Cutting groves in stone pillars	46	Each	
19.	Providing and fixing solid bamboos for barricading 6′.	100	,,	
20.	Teakwood eave board (9″ x ½″)	558	R.ft.	
21.	Providing and fixing head and heal rings ...	150	Each	
22.	Cutting quoins including extra thickness of plaster	276	S.ft.	